

BOARD OF EDUCATION

Julia C. Bernath, President
Kimberly Dove, Vice President
Gail Dean • Linda McCain • Katie Reeves
Katha Stuart • Franchesca Warren
Mike Looney, Ed.D., Superintendent

DATE: February 12, 2021

TO: All Contractors

FROM: Angela R. Young
Executive Director
FCS Capital Program Contracts

Handwritten signatures: Gail Dean, Linda McCain, Angela R. Young

RE: RFP 415-21, Abbots Hill Elementary School Fire Alarm Replacement

Please find Addendum No. 1 to the subject solicitation attached.

Addendum No. 1
RFP 415-21
Abbotts Hill Elementary School Fire Alarm Replacement

1. Addendum No. 1 has been issued for the above referenced project. Please contact the architect listed below:

Bolden Williams & Associates
3066 Highway 29 South
Lawrenceville, GA 30044
Attention: Jeff Williams
Phone: (770) 279-0413
Fax: (770) 925-4263
jwilliams@boden-williams.com

2. All other terms and conditions remain the same.

ADDENDUM #1 (February 12, 2021)

RE: RFP 415-21 ABBOTTS HILL ELEMENTARY SCHOOL - FIRE ALARM REPLACEMENT

FROM: FULTON COUNTY BOARD OF EDUCATION CAPITAL PROGRAM CONTRACTS
6201 Powers Ferry Road NW
Atlanta, GA 30339

TO: ALL PROSPECTIVE OFFERORS

This Addendum forms a part of the Contract Documents and modifies the Proposal Documents as noted below. Acknowledge receipt of the Addendum in the space provided on Document 00400 - Proposal Acceptance Form. Failure to do so may result in the proposal being deemed non-responsive. The Addendum consists of one (2) written page and the documents cited below:

- A. CHANGES TO PROPOSAL REQUIREMENTS TABLE OF CONTENTS: **NONE**
- B. CHANGES TO PRIOR ADDENDUM: **NONE**
- C. CHANGES TO PROPOSAL DOCUMENTS: **NONE**
- D. CHANGES TO CONDITIONS OF THE CONTRACT: **NONE**
- E. CHANGES TO DRAWINGS:
- F. CHANGES TO SPECIFICATIONS:
- G. OTHER CHANGES:
 - 1. Ceiling devices must be approved by the Fire Marshal. Provide bid per contract documents.
 - 2. Wiremold conduit transition at ceiling is required.
 - 3. Latest annual inspection of existing fire alarm system can be provided after bid.
 - 4. Lexan covers are required for all pull stations.
 - 5. As-built drawing on fire alarm system can be provided after bid.
 - 6. Audio/visual devices shall be red.
 - 7. All exposed cabling shall be in conduit. Cables above ceiling do not need conduit.
 - 8. Door holders are to be replaced.
 - 9. FACP conduit shall be wire mold.
 - 10. Only magnetic door hold-open devices are to be new.

Facility Code: 0101

11. **THERE WILL BE A SITE VISIT HELD AT ABBOTT'S HILL ELEMENTARY SCHOOL ON MONDAY, FEBRUARY 15TH AT 1:00 PM FOR OFFEROR'S WHO NEED TO GATHER ADDITIONAL INFORMATION ABOUT THE BUILDING EXISTING CONDITIONS.**

END OF ADDENDUM NO. 1